

4200

CHANDIGARH HOUSING BOARD
8, JAN MARG, SECTOR 9-D, CHD

SHORT QUOTATION NOTICE

Short quotations are hereby invited by the undersigned for under mention work from the contractor/manufacturers/OEMs/specialized job agencies of Chandigarh Housing Board, Chandigarh so as to reach in this office on 22-05-2023 at 3.00 PM. These shall be opened at the same time in the presence to the firms/contractors or their representatives who may like to be present at that time:-

App. Amount Rs. 64102/-

Name of work: ADDITION ALTERATION IN OFFICE BUILDING BLOCK 'B' OFFICE BUILDING CHB (DISMANTLING AND RE INSTALLATION OF SPLIT AIRCONDITINORS)

<u>Sr.No</u>	<u>Description</u>
	As per schedule attached

Conditions:

1. The work shall have to be completed according to CPWD specifications.
2. The undersigned reserved the right to accept or reject any or all the quotations without assigning any reasons.
3. Conditional quotations are not acceptable.
4. The Qty can be increased or decreased as desired by the Engineer-in-charge.
5. All disputes concerning in any way with the quotations will be subject to the Chandigarh jurisdiction.


Sub. Divisional Engineer,
Elect Sub Division No.III
CHB, Chandigarh.


Endst.No:

942819

Dated: 15/05/2023

Copy is forwarded to the following for information and wides publicity:

1. Notice Board.
2. The Executive Engineer-V (Elect,) CHB, Chandigarh
3. The computer- in- charge, CHB along with a copy of SCN and schedule to be uploaced on CHB website.
4. M/s Arjun Electrical.
5. M/s Bhumi enterprises
6. M/s chandla air condition


Sub Divisional Engineer,
Elect Sub Division No.III
CHB, Chandigarh

o/c


SCHEDULE

Addition Alteration in office building Block 'B' Office Building CHB (Dismantling and re installation of Split Airconditionors)

S. No.	Item Code	Description of Items	Qty	Unit	Rate	Rate to be quoted by agency
1	NS	Supply, Installation, testing and commissioning including vacuumization and Nitrogen testing of following nominal sizes of soft/hard drawn copper refrigerant piping Split Airconditioning system, complete with fittings, with suitable adjustable ring type hanger supports, jointing/brazing including accessories, insulated with XPLE Class-O tubular insulation/with Class-O closed cell elastometric nitrile rubber tubular sleeves sections as required : 9.5 mm dia (OD) (Soft drawn) with tube thickness 1.2 mm with 19 mm thick insulation	36.00 Mtrs	Metre	450.00	
(b)		15.86 mm dia (OD) (Soft drawn) with tube thickness 1.2 mm with 19 mm thick insulation	36.00 Mtrs	Metre	770.00	
2	NS	Dismantling of Existing 1.5/2 Ton Split Airconditioner installed in working condition with complete accessories and saving the gas as much as it can.	4.00 No.	Each	686.00	



3	NS	Installation of existing 1.5/2 Ton Split Airconditioner at given location including the cost of accessories/fasteners etc. The job also includes shifting of the same from other building at desired location including testing and commissioning.	4.00	No.	Each	797.00	
4	NS	Supplying and charging of Gas as per manufacturer standard.					
i)		1.5 Ton	2.00	No.	LS	1200.00	
ii)		2 Ton	2.00	No.	LS	1800.00	
5	NS	Providing & fixing of PVC Pipe complete with fittings, supports as per specifications as per direction of Engineer-in-charge & specifications enclosed as reqd.					
i)		25 mm dia	30.00	Mtrs	Metre	100.00	
6	NS	Supply and erection of three core copper cable 70/76	30.00	Mtrs	Metre	175.00	


 Sub Divisionat Engineer
 Electrical Sub Division No. III
 Chandigarh Housing Board
 Chandigarh