

**CHANDIGARH HOUSING BOARD**  
**8, JAN MARG, SECTOR 9-D, CHD**

**SHORT QUOTATION NOTICE**

Short quotations are hereby invited by the undersigned for under mentioned work from the agencies enlisted in UT Engineering department, MC Chandigarh, CPWD, MES, Punjab PWD, Haryana PWD, Himachal PWD, and other state government departments, Boards/corporations and PSUs, so as to reach in this office on 27.11.2023 at 3.00 PM. These shall be opened at the same time in the presence to the firms/contractors or their representatives who may like to be present at that time:-

App. Amount Rs. 91540/-

**Name of work: Special Repairs of HVAC System of Block'B' CHB office Building on Risk and Cost of M/s GSBA Builders Pvt Ltd**

| <u>Sr.No</u> | <u>Description</u>       |
|--------------|--------------------------|
|              | As per schedule attached |

**Conditions:**

1. The work shall have to be completed according to CPWD specifications.
2. The undersigned reserved the right to accept or reject any or all the quotations without assigning any reasons.
3. Conditional quotations are not acceptable.
4. The Qty can be increased or decreased as desired by the Engineer-in-charge.
5. All disputes concerning in any way with the quotations will be subject to the Chandigarh jurisdiction.

Sub. Divisional Engineer,  
Elect. Sub Division No.1  
CHB, Chandigarh.

Endst.No: 1267701.

Dated: 20/11/2023

Copy is forwarded to the following for information and vides publicity:


1. Notice Board.
2. The Executive Engineer-V (Elect,) CHB, Chandigarh.
3. Computer In-charge.
- 4.
- 5.

Sub Divisional Engineer,  
Elect. Sub Division No.1,  
CHB, Chandigarh

**Schedule of items for the work Special Repairs of HVAC  
System of Block 'B' CHB office Building on Risk and Cost of M/s GSBA Builders Pvt Ltd**


**Date of Opening; 27.11.2023**

| Sr. No. | DSR/MR    | Description                                                                                                                                                                                                                                                                                                     | Approx. Amount: 91540.00 |      |          |        |           |
|---------|-----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|------|----------|--------|-----------|
|         |           |                                                                                                                                                                                                                                                                                                                 | Qty.                     | Rate | Unit     | Amount |           |
| 1       | 16.12.2   | Supply, installation, balancing and commissioning of fabricated at site GSS sheet metal rectangular/round ducting complete with neoprene rubber gaskets, elbows, splitter dampers, vanes, hangers, supports etc. as per approved drawings and specifications of following sheet thickness complete as required. |                          |      |          |        |           |
|         | 16.12.2.1 | Thickness 0.63 mm                                                                                                                                                                                                                                                                                               | 3.6                      | Sqm  | 1058     | Sqm    | 3808.8    |
| 2       | 16.15     | Supplying & fixing of powder coated extruded aluminium Supply Air Grills with aluminium volume control dampers as per specifications.                                                                                                                                                                           | 2.88                     | Sqm  | 9105.00  | Sqm    | 26222.4   |
| 3       | 16.16     | Supplying & fixing of powder coated extruded aluminium Return Air Grills with louvers but without volume control dampers complete as required.                                                                                                                                                                  | 3.60                     | Sqm  | 5910.00  | Sqm    | 21,276.00 |
| 4       | 16.17     | Supplying, fixing, testing commissioning of supply air diffuser of power coated aluminium with aluminium volume control dampers with anti smudge ring & removable core.                                                                                                                                         | 0.72                     | Sqm  | 12184.00 | Sqm    | 8772.48   |

  
 Sub Divisional Engineer  
 Electrical Supply Division - I  
 Chandigarh : 27.11.2023  
 Chief Engineer

|   |         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |     |      |         |      |           |
|---|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|---------|------|-----------|
|   | 16.23   | Supplying and fixing of following thickness duly laminated aluminum foil of mat finish closed cell Nitrile rubber (Class "O") insulation on existing duct after applying suitable adhesive for Nitrile rubber. The joints shall be sealed with 50 mm wide and 3 mm thick self adhesive nitrile rubber tape insulation complete as per specifications and as required.                                                                                                                              |     |      |         |      |           |
|   | 16.23.1 | 19mm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 3.6 | Sqm  | 754.00  | Sqm  | 2714.4    |
| 6 | MR      | Extra for cutting gymsum ceiling 600mmx600mm for installation of Air Grills and making good the same. The job also includes making suitable size collar /dropper of GI sheet with minimum thickness of 0.63 mm to be fixed above the ceiling and making connection to the existing GI sheet duct including the cost of all petty material involved including rubber gasket,thread rod,Nut, washers, Self Drilling screws etc. to complete the job to the entire satisfaction of Engineer In Charge | 18  | Nos. | 1597.00 | Each | 28,746.00 |
|   |         | Total                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |     |      |         |      | 91,540.08 |

Say Rs.91540/-

  
 Sub Divisional Engineer  
 Electrical Sub-Division No. -1  
 Chandigarh Electricity Board

VR