

CHANDIGARH HOUSING BOARD
8, JAN MARG, SECTOR 9-D, CHD

SHORT QUOTATION NOTICE

Short quotations are hereby invited by the undersigned for under mentioned work from the agencies enlisted in UT Engineering department, MC Chandigarh, CPWD, MES, Punjab PWD, Haryana PWD, Himachal PWD, and other state government departments, Boards/corporations, PSUs, and other specialized agencies so as to reach in this office on 29.12.2023 at 3.00 PM. These shall be opened at the same time in the presence to the firms/contractors or their representatives who may like to be present at that time:-


App. Amount Rs. 80,887/-

Name of work: Special Repairs of HVAC Ducting and Piping in Block 'B' CHB office Building on Risk and Cost of M/s GSBA Builders Pvt Ltd

Sr.No	Description
	As per schedule attached

Conditions:

1. The work shall have to be completed according to CPWD specifications.
2. The undersigned reserved the right to accept or reject any or all the quotations without assigning any reasons.
3. Conditional quotations are not acceptable.
4. The Qty can be increased or decreased as desired by the Engineer-in-charge.
5. All disputes concerning in any way with the quotations will be subject to the Chandigarh jurisdiction.



Sub. Divisional Engineer,
Elect. Sub Division No. I
CHB, Chandigarh.

Endst.No: 1320808(i-iii)

Dated: 22/12/2023

Copy is forwarded to the following for information and vides publicity:

1. Notice Board.
2. The Executive Engineer-V (Elect.) CHB, Chandigarh.
3. Computer In-charge.


Sub Divisional Engineer,
Elect. Sub Division No. I,
CHB, Chandigarh



**Schedule of Items for the work of Special Repairs of HVAC Ducting and Piping in Block 'B'
CHB office Building on Risk and Cost of M/s GSBA Builders Pvt Ltd**

Date of Opening; 29.12.2023		Approx. Amount: 80887.00				
Sr. No.	Description	Qty.		Rate	Unit	Amount
1	Supply, installation, balancing and commissioning of fabricated at site GSS sheet metal rectangular/round ducting complete with neoprene rubber gaskets, elbows, splitter dampers, vanes, hangers, supports etc. as per approved drawings and specifications of following sheet thickness complete as required.					
	Thickness 0.63 mm	7.2	Sqm	1058	Sqm	7617.6
2	Supplying, fixing, testing commissioning of supply air diffuser of powder coated alluminium with aliminum volume control dampers with anti smudge ring & removable core.	1.44	Sqm	12184.00	Sqm	17544.96
3	Supplying and fixing of following thickness duly laminated aluminum foil of mat finish closed cell Nitrile rubber (Class "O") insulation on existing duct after applying suitable adhesive for Nitrile rubber. The joints shall be sealed with 50 mm wide and 3 mm thick self adhesive nitrile rubber tape insulation complete as per specifications and as required.					0
	19 m.m.	40	Sqm	697.00		27880.00
4	Supply, fixing and commissioning of Fresh/ exhaust air louvers with section comprising of powder coated Aluminium louvers & bird screen as required.	2.93	Sqm	7461.00		21860.73
5	Providing & fixing of PVC Pipe, heavy duty 25 mm dia complete with fittings, supports as per specifications. The pipe shall be laid above the false ceiling/ on wall to be fixed with saddles etc. as per requirement. The job also includes making connection of PVC pipe with disposal of water drainage from HVAC indoor unit.	32	Mtr.	187.00		5984.00
	Total					80,887.29

Say **80,887.00**


 Sub Divisional Engineer,
 Electrical Sub Division No. - I
 Chandigarh Housing Board

✓