

# CHANDIGARH HOUSING BOARD

## 8, JAN MARG, SECTOR 9-D, CHD

### SHORT QUOTATION NOTICE

Short quotations are hereby invited by the undersigned for under mention work from the contractor/manufacturers of Chandigarh Housing Board, Chandigarh so as to reach in this office on **07.02.2025** at **3.00 PM**. These shall be opened at the same time in the presence to the firms/contractors or their representatives who may like to be present at that time -

App. Amount Rs.79,142/-

**Name of work:** Providing Main Supply & Additional Earthing Required for Installation of 2Nos. Lift at Hotel Beckon, Sector-42 D, Chandigarh.

Sr.No	Description
-------	-------------

As per schedule attached

### Conditions:

1. The work shall have to be completed according to CPWD specifications.
2. The undersigned reserved the right to accept or reject any or all the quotations without assigning any reasons.
3. Conditional quotations are not acceptable.
4. The Qty can be increased or decreased as desired by the Engineer-in-charge.
5. All disputes concerning in any way with the quotations will be subject to the Chandigarh jurisdiction.

*sd.*  
Sub. Divisional Engineer,  
Elect Sub Division No IV  
CHB, Chandigarh

Endst.No: 1960963

Dated: 04/02/2025

Copy is forwarded to the following for information and vides publicity:

1. Notice Board.
2. The Executive Engineer-V (Elect,) CHB, Chandigarh.
3. M/s Arjun Electricals Baltana
4. M/s Mohali Construction Co.
5. M/s V.K. Contractor, Chandigarh.
6. computer incharge.

*sd.*  
Sub. Divisional Engineer,  
Elect Sub Division No IV  
CHB, Chandigarh



**NAME OF WORK:- PROVIDING MAIN SUPPLY & ADDITIONAL EARTHING REQUIRED FOR INSTALLATION  
OF 2NOS. LIFT AT HOTEL BECKON, SECTOR-42, CHANDIGARH**

**SCHEDULE OF WORK**

Sr.No.	Ref of DSR/NS		Qty.	Unit	Rates to be quoted by the contractor
		<b>WIRING.</b>			
1	1.7 (E & M. 2022)	Wiring for circuit/submain wiring along with earth wire with the following size of FRLS PVC insulated copper conductor, single core cable in surface /recessed steel conduit as required.			
	1.7.9	4X6 sq mm +2X6 sqmm earth wire	19.6 Mtr	P/mt	
		<b>MCCB/ MCB &amp; DB's</b>			
2	2.3	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator)			
	2.3.1	6 way, Double door	2 Nos.	Each	
3	2.15	Supplying and fixing following rating, four pole, (three phase and neutral), 415 volts, residual current circuit breaker (RCCB), having 40 A	2 Nos.	Each	
	2.15.2				
		<b>EARTHING</b>			
4	5.14	Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required.	40 Nos.	Each	

Sub-Divisional Engineer  
Electrical Sub-Division IV  
Chandigarh Housing Board  
Chandigarh

*(Signature)*